

**SURVEY & REMONUMENTATION**

MAY 05 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **F4** PAGE **125**

For corners in

ST. JOSEPH (County) Located In: Corner Code **≠#**  
 NOTTAWA TWP.  
 1. Public Land Survey T 6S R 10W K-7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

12 APR 95 3:16 P.M.

CYNTHIA JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID W. MOSTROM, in a field survey on APRIL 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(K-7) NW COR. SEC. 24  
1865 SURVEY IN BOOK A, PG. 129  
 "STAKE" - NO WITNESSES  
1892 SURVEY IN BOOK A, PG. 582  
 STONE SET IN REMAINS OF ORIG. POST  
 NO WITNESSES

1963 ROAD COMMISSION  
 1/2" PIPE OVER STONE IN MON. BOX  
 RR ANCHOR POST = N40°W 43.85'  
 25" OAK = N25°W 67.74'  
 8" WOOD ANCHOR POST = SOUTH 28.33'  
 7" HICKORY = S65°W 54.13'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-7)  
 FOUND POINTED STONE IN MON. BOX IN FENCE LINE PROJ. TO SOUTH  
 CORNER IS 1.5' N. OF THE CL OF E-W ROAD AND 5' EAST OF CL ROAD TO NORTH  
 R.R. ANCHOR POST = N40°W 43.85'  
 25" OAK (STUMP) = N25°W 67.74'  
 8" WOOD ANCHOR POST = SOUTH 28.33' (FACE)  
 7" HICKORY = S65°W 54.13'

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON April 10, 19 95  
Wade CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-7) NW COR. SEC. 24  
 SET 5/8" X 14" IRON BAR W/STD. CAP OVER STONE IN MON. BOX  
 N & W 1.5' HIGH ON E. SIDE OF 34" OAK STUMP = N25°W 67.74'  
 N & W 1.0' HIGH ON W. SIDE OF 8" ANCHOR POST = SOUTH 28.74'  
 N & W 1.5' HIGH ON N. SIDE OF 18" HICKORY = S65°W 54.13'  
 N & W 0.5' HIGH ON N. SIDE OF 4" HICKORY = S49°E 47.35'



LIBER **4** PAGE **125**

Signed by J.W. Mostrom Date APRIL 11, 1995

Surveyor's Michigan License No. 32339

REMONUMENTATION