

NOV 15 1994

004 PG 055

FILED

SEP 29 4 54 PM '94

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Cynthia R. Janett  
REGISTER OF DEEDS  
ST. JOSEPH CO MICH

for corners in

ST. JOSEPH (County)	Located In:	Corner Code #
NOTTAWA TWP. Public Land Survey	T 6 S R 10 W	L-5
	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

WAYNE A. MOSTROM, in a field survey on SEPTEMBER 7, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

<u>L-5</u>	<u>ROAD COMMISSION-1961</u>	<u>1976 L.C.R.C.-L-3, P-53</u>
<u>GLO</u>	1/2" PIPE OVER LARGE STONE IN MON. BOX	PIPE IN MON. BOX
12" RED OAK = S61°W 15 LKS	17" WAL. = S40°E 31.74'	A.P. = SOUTH 28.8'
16" RED OAK = N43°E 54 LKS	8" OAK = S5°E 49.80'	16" WAL. = SE 31.0'
	12" OAK = S30°W 43.00'	N. END CULVERT = NE 23.1'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5  
FD. 1/2" PIPE OVER STONE IN MON. BOX  
N. END 14" CMP = N33°E 23.1'  
26" DBL. WAL. = S32°E 31.97'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON Sept. 12, 1994  
Wayne CO. REPRESENTATIVE

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5  
SET 5/8" X 24" BAR W/STD. CAP IN MON. BOX  
N. END 14" CMP = N33°E 23.1'  
26" DBL. WAL. = S32°E 31.97'  
24" DBL. HICK. = S20°W 51.0'  
14" HICK. = S35°W 42.95'  
18" W.O. = S53°W 60.0'  
1/2" ASPHALT RDWY = SOUTH 1.5'  
P.K. NAILS & WASHERS WERE SET IN ALL WITNESS TREES

CORNER IS 1' W. OF FENCE LINE TO SOUTH

Signed by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date 9/14/94

