

NOV 15 1994

LIBER 4 PAGE 60

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH (County)

Located In:

Corner Code #

NOTTAWA TWP.

1. Public Land Survey

T 6S R 10W

M-3

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

STATE OF MICHIGAN ST. JOSEPH COUNTY FILED

18 OCT 94 2:29 P.M.

CYNTHIA JARRATT REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 6-36.

DAVID W. MOSTROM in a field survey on OCTOBER 3, 1994 to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

(M-3) SE COR. SEC 1 T6S, R10W

NO EVIDENCE OF GLO WITNESSES

1879 SURVEY-BOOK A, PG. 300

1876 SURVEY - BOOK A, PG. 244

STONE BY FORMER SURVEYOR

3" W. OAK = N42°E 0.76

STONE

3" BLK WALNUT = S62°W 57 LINKS 1961 - MDOT

FOUND AXLE SHAFT

ROAD SIGN POST = N17°E 98.51'

RR ANCHOR POST = WEST 31.93'

COLON TWP. COR. = NORTH 60.72' CONST. CL = WEST 36.26'

1976 SURVEY BY PS #14100 & LCRC IN BOOK 3, PG. 53

IRON BAR COLON CORNER = NORTH 60.72'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-3)

FOUND 1/2" X 18" IRON BAR 60.72' SOUTH OF COLON TWP. CORNER IN DITCH OF HIGHWAY

RATIFIED BY PEER GROUP IN ACCORDANCE WITH P.A. 345 ON OCT. 10, 1994 Wilson CO. REPRESENTATIVE

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-3) SE COR. SEC. 1 T6S, R10W

SET 5/8" X 24" IRON BAR W/STD. CAP

IRON ANCHOR POST = N79°E 146.40'

IRON ANCHOR POST = S10°E 153.50'

P. POLE = N53°W 116.70'

E. EDGE PVMT = WEST 10.30'

COLON TWP. COR. = NORTH 60.72'

HWY. CL = WEST 36'



signed by [Signature]

Date OCTOBER 12, 1994

Surveyor's Michigan License No. 32339