

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 140

For corners in ST. JOSEPH Located In: Corner Code #
(County)
NOTTAWA TWP.

1. Public Land Survey	T	<u>6S</u>	R	<u>10W</u>	<u>M-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED
11 MAY 95 4:21 P.M.
CYNTHIA JARRATT
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID W. MOSTROM, in a field survey on JANUARY 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-7) NE COR. SEC. 24, NOTTAWA TWP.

<u>GLO</u> JOG TO COLON TWP. COR. = NORTH 61.38' <u>1865 SURVEY IN BOOK A, PG. 128</u> STONE FROM ORIG. BRG. TREES 2" HICKORY = S45°W 59 LINKS	<u>1961 MDOT</u> FOUND P.K. NAIL & CAP SET BY OTHERS A. POST = N70°W 70.67' A. POST = N30°E 82.62' 13" OAK = S70°W 86.75' COLON TWP. COR. = NORTH 72.75'	<u>1964 MDOT</u> SURVEY CENTERLINE: WEST 3.3' COLON TWP. COR. = NORTH 72.75'
--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-7)

FOUND 1" PIPE IN MON. BOX
COLON TWP. COR. = NORTH 72.79'
CENTERLINE HWY. M-66 = WEST 3.3'
A. POST = N30°E 82.62'±

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 348
ON MAY 8th, 1995
W. M. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-7) NE COR. SEC. 24, NOTTAWA TWP.

SET 5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX IN PLACE OF 1" PIPE
CONC. R/W MARKER = S62°E 58.12'
CENTERLINE OF WASEPI ROAD = SOUTH 3'±
N & W 6' HIGH ON S. SIDE OF 12" OAK = S60°E 58.80'
N & W 6' HIGH ON NE SIDE OF 4" ELM = S30°E 107.75'
N & W IN TOP OF FENCE POST = S45°E 73.47'
COLON TWP. COR. = NORTH 72.79'



Signed by J. W. Mostrom Date MAY 9, 1995

Surveyor's Michigan License No. 32339

REMONUMENTATION

LIBER 4 PAGE 140