

SURVEY & RECORDATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 137

For corners in ST. JOSEPH COMMISSION (County)

Located In: Corner Code #

NOTTAWA TWP.

1. Public Land Survey	T	6	S	R	10	W	M-8
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Section	S		T		R		
	S		T		R		

STATE OF MICHIGAN ST. JOSEPH COUNTY FILED

11 MAY 95 4:16 P.M.

CYNTHIA JARRATT REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, DAVID W. MOSTROM, in a field survey on APRIL 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-8) EAST 1/4 COR. SEC. 24 NOTTAWA TWP.

1865 SURVEY IN BOOK A, PG. 128

1979 MOSTROM SURVEY & LCRC IN BOOK 2, PG. 110

STONE MARKED + EQUIDISTANT BETWEEN NE & SE SECTION COR'S. 18" W. OAK = N76 3/4°W 19.14'

FOUND IRON BAR IN MON. BOX F.P. = NW 38.08' CONC. R/W MARKER = NW 36.40' CONC. R/W MARKER = NE 64.0' NW COR. HSE. = SE 62.2'

MDOT

HWY. C = EAST 2.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-8)

FOUND BOAT SPIKE IN MON. BOX EXISTING HWY. C = EAST 3.0' COLON TWP. COR. = NORTH 46.07' CONC. R/W MARKER = NE 64.0'

RATIFIED BY PEER GROUP IN ACCORDANCE WITH P.A. 345 ON MAY 8th, 1995 Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-8) EAST 1/4 COR. SEC. 24 NOTTAWA TWP.

SET 5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX IN PLACE OF BOAT SPIKE EXISTING HWY. C = EAST 3.0' COLON TWP. COR. = NORTH 46.07' 3/4" SHEARED PIPE = S48°E 38.58' 3/4" PIPE = N34°E 84.58' CONC. R/W MARKER = N84°E 63.89' N & W 3.0' HIGH IN S. SIDE OF P. POLE = N75°E 63.95'



Signed by [Signature]

Date MAY 10, 1995

Surveyor's Michigan License No. 32339

REMONUMENTATION

75th 1995