

REMC... ..

NOV 04 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 5 PAGE 21

For corners in

ST. JOSEPH

Located In:

Corner Code #

(County)  
Lockport Twp.

1. Public Land Survey

T 65 R 11W

B-1

T R

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

17 SEP 97 3:27 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on SEPT. 9, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1	⊙											
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

NO CORNER SET  
ON GLO SURVEY

MULTIPLE SURVEYS BY  
R.E. SAYERS USED  
IRON BUT HAD NO  
WITNESSES

1982 SURVEY BY MOSTROM  
FOUND 1" IRON 72.6' EAST OF S 1/4 CORNER,  
SEC. 31  
SE COR. HSE = N73°E 32.25'  
SW COR. HSE = N17°E 9.21'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 5/8" PIPE 72.60' EAST OF B-13  
CORNER CHECKS INTO ADJACENT "SHADY BROOK SUB. NO. 1"  
COR. IS IN CENTERLINE OF ROADSAY TO WEST

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON SEPT. 8, 1977  
W.A. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 24" IRON W/STD. COUNTY CAP  
SW COR. HOUSE = N17°E 9.20'  
SE COR. HOUSE = N73°E 32.21'  
N&W IN NW SIDE TELE POLE = S30°W 37.42'  
N&W IN NE SIDE TELE POLE = N70°W 110.82'  
1/2" IRON BAR = SOUTH 33'



LIBER 5 PAGE 21

Signed by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date SEPTEMBER 11, 1997