

SURVEY & REMONUMENTATION

APR 10 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH
 (County)

Located In:

Corner Code #

LIBER 4 PAGE 84

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

20 DEC 94 12:37 P.M.

CYNTHIA JARRATT
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

1. Public Land Survey	T 6S R 11W	D-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		⊙										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, WAYNE A. MOSTROM in a field survey on DECEMBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1897 SURVEY BY TODD
 "STONE BY FORMER SURVEYOR"

1975 L.C.R.C. (3/60) &
1976 L.C.R.C. (2/61)
 FD. STONE IN E-W FENCE LINE
 28" OAK = N80°W 4.45'
 26" OAK = WEST 6.45'
 18" OAK = S10°E 1.55'
 ANCHOR POST = EAST 1.28'

1977 SURVEY BY SAYERS
 28" OAK = N80°W 4.45'
 26" OAK = WEST 6.45'
 18" OAK = S10°E 1.55'

1950'S SURVEY BY WHITE
 "STONE"

1978 SURVEY BY SAYERS
 20" OAK = NW 4.42'
 ANCHOR POST - EAST 1.27'
 18" OAK = SE 1.53'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE (BROWN IN COLOR) 11" LONG W/6" BASE

28" OAK = N80°W 4.45'
 26" OAK = WEST 6.45'
 18" OAK = S10°E 1.55'
 ANCHOR POST = EAST 1.28'
 COR. IS IN E-W FENCE (ONE & IN REMAINS OF FENCE RUNNING SOUTH

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON DEC. 12, 1994
Wayne A. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 24" IRON BAR W/STD. CAP OVER STONE

N & W IN 28" OAK = N80°W 5.27'
 N & W IN 26" OAK = WEST 7.35'
 N & W IN 18" OAK = S10°E 2.09'
 N & W IN ANCHOR POST = EAST 1.86'
 N & W IN 6" ELM = S10°E 16.31'
 COR. IS IN REMAINS OF FENCE (ONE TO EAST & SOUTH



LIBER 4 PAGE 84

Signed by Wayne A. Mostrom
 Surveyor's Michigan License No. 14100

Date DECEMBER 13, 1994

REMONUMENTATION