

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>St. Joseph</u>	Located In:	Corner Code #
(County)		
Lockport Twp.		
1. Public Land Survey	T <u>6</u> S R <u>11</u> W	<u>D-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER 5 PAGE 151
 STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

27 APR 1999 1:19:18 PM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David W. Mostrom, in a field survey on Mar. 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (D-11) 1/4 corner common to Sections 29 & 32 T6S, R11W

*GLO Post	*1864 Survey In Book A, Page 50
7" Y. Oak = N7 1/2°W 270.6'	Post
8" W. Oak = N34°E 204.6'	10" W. Oak = N34 1/2°E 216.15'
	10" W. Oak = N 1/4°E 293.7'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 0.2' Dia. x 1.5' long stake with sharpened point in low-wet area.
 NW Cor. Sec. 32 = N89°54'44"W 2640.34'
 NE Cor. Sec. 32 = S89°53'08"E 2640.28'
 Set 5/8" x 48" Iron bar w/std. cap inside 1" x 48" pipe in place of stake

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D-11) 1/4 corner common to Sections 29 & 32 T6S, R11W
 5/8" x 48" Iron bar w/std. cap Inside 1" x 48" pipe
 R.R. tie anchor post = S65°E 129.32'
 SW cor. gar. = N10°E 316.90'
 SE cor. gar. = N29°E 315.45'
 5" Cedar = N22°E 111.40'
 Remains of N-S fence = East 10.5'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
 ON April 19, 1999
WALKER CO. REPRESENTATIVE

LIBER 5 PAGE 151

Signed by J. W. Mostrom David W. Mostrom Date April 26, 1999
 Surveyor's Michigan License No. 32339

REMONUMENTATION