

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 6 PAGE 27

For corners in

St. Joseph
 (County)
Lockport Twp
1. Public Land Survey

Located In: Corner Code #

T 6S R 11W E-2

2. Property Controlling
 in Section
 3. Miscellaneous
 Property in Sec.

S T R
 S T R
 S T R
 S T R

**SURVEY &
 REMONUMENTATION**
JAN 31 2001

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

29 MAR 2000 10:15:33 AM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SECTION

I, Wayne A. Mostrom, in a field survey on Sept. 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5	⊕	4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

<u>GLO - Post</u>	<u>Sayers 1973 Survey</u>	<u>LCRC in 2/147</u>
6" Hick=N84°E 60lks (39.60')	Set RR Spike per Sec. Breakdown on E-W ¼ line using Center & & E¼ Cor & on line bet SW & NW Sec. Corners	dated 5/22/81 1/2" Bar in Mon. Box 18" Maple - N2°W 19.6' 7" Spruce - S15°E 55.5' 10" Osage Orange - N38°W 41.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found all witnesses shown in LCRC above
 Found 1/2" X 18" bar in Mon. Box
 Dug 48" deep but found nothing additional
 Remains of wire fence to North = West 3'
 Centerline E-W Asphalt Roadway = South 2.5'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON Sept, 13, 1999
Wayne A. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X 24" iron bar w/std. cap in mon. box in place of iron found.

N & W in W. side 30" Maple = N2°W 19.60'
 N & W in W. side 15" Cedar = S15°E 55.5'
 N & W in W. side 20" Locust = N38°W 41.8'
 N & W in N. side P.P. = S76°W 140.00'



LIBER 6 PAGE 27

Signed by Wayne A. Mostrom
 Surveyor's Michigan License No. #14100

Date 3/15/00

REMONUMENTATION