

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 5 PAGE 164

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

7 JUN 1999 10:42:28 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>St. Joseph</u> (County)	Located in:	Corner Code #
Lockport Twp. 1. Public Land Survey	T 6S R 11W	E-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David W. Mostrom, in a field survey on 4/30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (E-12) 1/4 Corner common to Sections 32 & 33 T6S, R11W
 *GLO Corner *1864 Survey in Bk A, Pg 62
 7" Burr Oak = S12½°E 28.38' Stake from old bearings
 12" Y. Oak = N5°E 84.48' now green
 16" Bl. Oak = S12½°E 28.38'
 14" Y. Oak = N05°E 84.48'

*1886 Survey in Bk A, Pg 508
 Old stake surrounded with
 stones set by a former surveyor
 B. Oak = S12½°E 28.38'
 Set W. Oak stake in place
 of old one

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Excavated in area of split between NE cor. & SE cor. of Sec. 32 -
 Found circle of cobbles and remains of stake running from
 a depth of 1.0' to 3.0'.
 Anchor post (fences running West & South) = S25°W 1.33'
 NE Cor. Sec. 32 = N00°05'10"W 2655.13'
 SE Cor. Sec. 32 = S00°09'50"E 2655.32'
 Capped iron #33967 next to Anchor Post = S33°W 1.50'
 Set 5/8" x 48" iron bar w/std. cap through remains of stake



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-12) 1/4 Corner common to Sections 32 & 33 T6S, R11W
 5/8" x 48" iron bar w/std. cap
 N & W 0.5' high on E. side of Anchor post = South 1.33'
 N & W 3' high on N. side of 18" Oak = S87°E 36.65'
 N & W 2' high on E. side of 6" Maple = S08°E 15.27'
 N & W 2' high on S. side of 12" Cherry = N87°W 6.46'
 N & W 3' high on W. side of 16" Dbl. Cherry = N40°E 10.76'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON May 10, 1999
CO. REPRESENTATIVE

LIBER 5 PAGE 164

Signed by J.W.M. David W. Mostrom
 Surveyor's Michigan License No. 32339

Date May 20, 1999

REMONUMENTATION