

SURVEY & REMONUMENTATION **LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 85

For corners in

ST. JOSEPH

located in:

Corner Code #

1. Public Land Survey 6S R 11W G-5
 T ___ R ___
 T ___ R ___
 T ___ R ___
2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___
3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

20 DEC 94 12:38 P.M.

CYNTHIA JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on NOVEMBER 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1903 SURVEY BY TODD

"STAKE & STONE"

5" RED OAK = N14 1/2° E 16LKS

12" RED OAK = S7 1/2°W 43 1/2"

1904 SURVEY BY REED

STONE

7" OAK = N14 1/2°E 15 3/4 LKS

14" OAK = S7 1/2°W 43 1/2 LKS

1975 PLAT OF EBY RIVER

IRON ROD IN CONC. MON.

1959 PLAT OF SHADY ACRES

(MONUMENT SYMBOL ON MAP)

1975 L.C.R.C. (3/65) & SURVEY

FOUND SQUARE MONUMENT

5" OAK = SOUTH 3.20'

N. EDGE/BOULDER = SOUTH 0.7'

16" PINE = SW 17'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" X 4" CONC. MONUMENT ENCASING 5/8" IRON BAR

5" OAK = SOUTH 3.2' (NOW A STUMP)

6" PINE = SW 17' (NOW A STUMP)

COR. IS IN CL OF HWY. M-60 PROJECTED EASTERLY

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON DEC. 12, 1994
 _____ CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED STD. CAP ON EXIST. 5/8" BAR IN 4" X 4" CONC. MON.

N & W IN 29" BLK. OAK = S19°W 54.48'

N & W IN 18" RED OAK = S72°W 73.96'

N & W IN 18" BLK. OAK = S70°E 29.75'

N & W IN 8" BLK. OAK = N67°E 10.22'

MONUMENTS = SOUTH 5.39' AND SOUTH 59.94'

COR. IS IN CL HWY. M-60 TO THE WEST



Signed by Wayne A. Mostrom

Date DECEMBER 13, 1994

Surveyor's Michigan License No. 14100

REMONUMENTATION

LIBER 4 PAGE 85