

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in LOCKPORT TWP.

LIBER 5 PAGE 165

ST. JOSEPH CO.
(County)

Located In:

Corner Code #

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

7 JUN 1999 10:42:49 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	T	6	S	R	11	W	H-7
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

DAVID W. MOSTROM in a field survey on APRIL 30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H-7) 1/4 CORNER COMMON TO SECTIONS 15 & 22 T 6 S, R 11 W

- *1960'S ROAD COMMISSION LARGE STONE & STAKE IN MON. BOX P. POLE = N55°E 34.85' ANCHOR POST = S07°E 32.69' 28" HICKORY = S58°E 50.61'
- *1969 DNR NOTES MON. BOX WITH POINTED ROCK 18" HICKORY = NORTH 26.0' P. POLE = N52°E 35.3' 24" HICKORY = S50°E 49.0' (FACE)
- *1993 MOSTROM SURVEY FOUND STONE IN MON. BOX 26" HICKORY=NORTH 25.90' 36" HICKORY=S70°E 48.96' TELE. POLE=S10°E 30.45' TELE. POLE=N50°E 35.37' CORNER FALLS IN CENTER-LINE OF S. RIVER RD. & IN PROJ. OF FENCELINE TO THE NORTH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND POINTED STONE IN MON. BOX ANCHOR POST = S07°E 32.69' (TO FACE) 36" HICKORY = S70°E 48.96' 30" HICKORY = NORTH 25.90' CORNER FALLS IN CENTERLINE OF S. RIVER RD. & IN PROJ. OF FENCELINE TO THE NORTH SET 5/8" X 5" IRON BAR WITH STD. CAP IN CONC. OVER STONE IN MON. BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-7) 1/4 CORNER COMMON TO SECTIONS 15 & 22 T 6 S, R 11 W

- 5/8" X 5" IRON BAR WITH STD. CAP IN CONC. OVER STONE IN MON. BOX N & W 1.5' HIGH IN W. SIDE OF 30" HICKORY = NORTH 25.90' N & W 1.5' HIGH IN NE SIDE OF 12" OAK = N50°W 56.43' N & W 1.0' HIGH IN W. SIDE OF 36" HICKORY = S70°E 48.96' N & W 1.0' HIGH IN E. SIDE OF 8" ELM = S15°W 35.29'



RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON May 10, 1999
Allen CO. REPRESENTATIVE

LIBER 5 PAGE 165

Signed by J.W.M.

DAVID W. MOSTROM

Date MAY 10, 1999

Surveyor's Michigan License No. 32339

REMONUMENTATION