

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

St. Joseph (County) Located In: Corner Code #
Lockport Twp.
1. Public Land Survey T 6S R 11W 1-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

LIBER 5 PAGE 166

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

7 JUN 1999 10:43:11 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, David W. Mostrom, in a field survey on 4/30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column I and row 7.

A. Description of original monument and accessories and/or subsequent restoration:

- (I-7) Corner common to Sections 14, 15, 22 & 23 T6S, R11W
*GLO Corner
7" W. Oak = S62 1/2 E 91.08'
15" W. Oak = N82 1/2 W 68.64'
*1947 Jay White Survey
Iron pipe over top of stone
*Sayers old witness book - no date
Stone & Iron pipe
U.S.G.S. BM = NW 46.2'
35" Maple = SW 34.1'
*1960's Road Commission
1/2" pipe over stone in Mon. box
NE cor. house = S44 W 54.2'
SE cor. Twp. Hall = N37 W 104.8'
Anchor post = N41 E 42.05'
*1969 DNR Records
3/4" pipe in Mon. box
Stop sign = S70 W 33.4'
USGS BM = N45 W 46.2'
Fence post = N40 E 42.2'
10" CMP = S70 E 89.7'
*1975 LCRC in Bk 3, Pg 69
Found box with pipe
USGS marker 825-
N45 W 46.25'
Anchor post =
N45 E 42.25'
Cor. falls in E-E roads
*1974 LCRC in Bk 3, Pg 74
Found bar in box
Anchor = NE 42.3'
In E road
USGS 825 = NW 46.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 7" pipe over large notched stone in Mon. box
U.S.G.S. Benchmark = N45 W 46.23'
Anchor post = N41 E 42.2'
Stop sign = S70 W 33.4'
10" CMP = S70 E 89.7'
Corner falls in E of Strobel Rd. to the North & in the E of S. River Rd.
Set 5/8" x 7" iron bar w/std. cap in conc. over stone in Mon. box

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON May 10, 1999
Wagon CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I-7) Corner common to Sections 14, 15, 22 & 23 T6S, R11W
5/8" x 7" iron bar w/std. cap in conc. over stone in Mon. box
USGS Benchmark = N45 W 46.23'
SE cor. Lockport Twp. Hall = N39 W 104.97'
NW Cor. garage = S38 E 135.90'
N & W 1.5' high in S. side of P. Pole = N74 E 116.95'



LIBER 5 PAGE 166

Signed by [Signature] David W. Mostrom
Surveyor's Michigan License No. 32339

Date May 20, 1999

REMONUMENTATION