

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Lockport Twp.

**LIBER 6 PAGE 10**  
STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED  
7 JAN 2000 9:48:33 AM  
CYNTHIA L. JARRATT  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

<u>St. Joseph</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6S</u> R <u>11W</u>	<u>1-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Wayne A. Mostrom, in a field survey on 8/4, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1904 Survey in B/126  
Could not be found -  
not marked  
79.87 Ch. W. of NE Cor.

Road Comm. 1962  
1" pipe in Mon. box  
A.P. = N40°W 39.7'  
A.P. = S41°W 41.1'  
NW hse. cor. = S37°E  
103.7'

Sayers 1962 Records  
Pointed sto. 2" deep  
5" Oak = NW 37.85'  
4" Oak = N10°E 13.16'  
16" Sass. = S. 73.5'

1974 LCRC in 1/107 & 3/74  
Mon. box over pipe found  
in  $\zeta$  Holtom Rd. & M-86  
1980 Survey by Mostrom  
1" pipe in Mon. box  
P.P. = S40°E 59'  
Tele. Pole = N45°E 48.4'  
Cor. is in  $\zeta$  pavement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1 1/2" x 13" pipe in Mon. box @  $\zeta$ - $\zeta$  Intersec.  
Dug down 54" and found nothing.  
NW cor. hse. = S37°E 103.7'  
P.P. = S40°E 59'  
Tele. Pole = N45°E 48.4'

**RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON AUG. 9, 1999**  
W.A. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" bar w/std. cap in Mon. box  
N & W in E. side P.P. = S28°E 59.35'  
N & W in NW side Tele. pole = N37°E 48.77'  
N & W in E. side 31" Walnut = N11°W 80.37'  
NW cor. hse. fdtn. = S38°E 103.86'



LIBER 6 PAGE 10

Signed by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date Dec. 30, 1999

**REMONUMENTATION**