

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Lockport Twp.

St. Joseph Co. (County)	Located In:	Corner Code #
1. Public Land Survey	T 6S R 11W	K-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 5 PAGE 167

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

7 JUN 1999 10:43:32 AM

CYNTHIA L. JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David W. Mostrom, in a field survey on 4/30, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (K-7) Corner common to Sections 13, 14, 23 & 24 T6S, R11W
- \*GLO Corner
  - 10" W. Oak - South 6.6'
  - 15" W. Oak - N07°E 28.38'
- \*1974 LCRC in Bk 3, Pg 74
  - Pipe in box found
  - P. Pole = SW 36.90'
- \*1974 LCRC in Bk 1, Pg 135
  - Box & pipe found
  - Anchor post = NW 44.4'
  - Tele. box = NE 40.75'
  - Anchor post = South 32.8'
- \*1989 LCRC in Bk 2, Pg 234
  - Found 3/4" pipe in Mon. box
  - P. Pole = S33°W 37.33'
  - A. Post = South 32.81'
  - 12" Oak = N17°W 65.41'
  - 12" Pine = S42°30'E 47.83'
- \*1963 Road Commission
  - Large stone in Mon. box
  - Anchor post = N39°W 44.0'
  - Anchor post = S03°W 32.5'
  - 33" Oak = N15°E 60.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 11" pipe over stone in Mon. box  
 Anchor post = S03°W 32.5' (to face) 32.81' to P.K.  
 P. Pole = S33°W 37.33'  
 C of South River Road = South 1.5'  
 17" Pine = S42°30'E 47.83'  
 C Jacobs Road to North = East 4'  
 Set 5/8" x 10" iron w/std. cap in conc. over stone in Mon. box



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-7) Corner common to Sections 13, 14, 23 & 24, T6S, R11W  
 5/8" x 10" Iron w/std. cap in conc. over stone in Mon. box  
 N & W 2' high in W. side of anchor post = S03°W 32.81'  
 N & W 2' high in SW side of P. Pole = S33°W 37.33'  
 N & W 2' high in NE side of 17" Pine = S42°30'E 47.83'  
 N & W 2' high in E. side of P. Pole = N10°W 122.45'

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON May 10, 1999  
Wills CO. REPRESENTATIVE

LIBER 5 PAGE 167

Signed by J. D. W. Mostrom David W. Mostrom  
 Surveyor's Michigan License No. 32339

Date May 20, 1999

REMONUMENTATION