

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>St. Joseph</u> (County)	Located In:	Corner Code #
<u>Lockport Twp.</u>	T <u>6S</u> R <u>11W</u>	<u>K-8</u>
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER **5** PAGE **154**

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

27 APR 1999 1:20:24 PM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Wayne A. Mostrom, in a field survey on March 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

<u>GLO</u>	<u>ROAD COMMISSION-1962</u>	<u>1975 LCRC in 1/107</u>	<u>MOSTROM 1989 SURVEY</u>
Set Post	Stone with Plus	& <u>3/74 & SAYERS 79 Survey</u>	
7" Hick-S12°W 51lks (33.60')	32" Pine - N55°W 128.52'	+ Stone & Brick found	Refers to LCRC in 1/107
15" Burr O. - N35°E	N. Rail of RR=South 30.8'	12" Cherry - SW 39.7'	CL Major Rd=N 17.0'
15 lks (9.9')	Sq. A.P. - N01°W 47.2'	Anchor RR Tie = N 47.1'	Stone found w/"+"
	SE Cor Hse = N32°W 99.54'	S. edge RR Rail=S 36'	
		SW Cor Hse = NW 92.0'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" X 18" Iron Bar leaning over "+" Stone 12" deep
 17.6' South of Road centerline. Corner is in line with edge/woods
 to South & Treeline to North
 Sq. A.P. = N01°W 47.2'
 Old SE Corner of House = N32°W 99.54'
 RR Rail is out but other witnesses on LCRC's check

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON APRIL 19, 1999
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Lowered +d stone & set over it a 5/8" x 24"
 bar w/std. cap in Mon. box
 N & W in N. side 22" Cherry - S74°W 39.70'
 SW Cor. brick chimney - N27°W 93.42'
 N & W in N. side 14" Blk. Oak - S81°E 78.5'
 N & W in E. side P.P. = S9°W 51.95'



LIBER **5** PAGE **154**

Signed by Wayne A. Mostrom
 Surveyor's Michigan License No. 14100

Date March 26, 1999

REMONUMENTATION