

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
<u>LOCKPORT TWP.</u>		
1. Public Land Survey	<u>T6S R11W</u>	<u>M-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER **4** PAGE **249**

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

12 SEP 96 8:53 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

WAYNE A. MOSTROM in a field survey on SEPT. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

LCRC BY MOSTROM IN 1975 (1/135)

1969 SURVEY BY SAYERS

PIPE IN MON. BOX
P.P. = NW. 50.6'
A.P. = SW. 48.0'

SHOWS COR. 62.7' SOUTH OF
SW. COR. SEC. 18 AS FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 3/4" X 25" PIPE IN MON. BOX OVER STONE 31" DEEP MARKED W/YELLOW PAINT COR. IS 2' S. OF CL RDWY. TO WEST & IN CL N-S RDWY.
A.P. = SW. 48.0'
SW. COR. SEC. 18 MEASURES 62.74' NORTH

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Sept. 9, 1996
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 24" BAR W/STD. COUNTY CAP IN MON. BOX
SE. COR. HSE. = N38°W 114.86'
N & W IN SW. SIDE 30" MAPLE = N53°W 128.8'
N & W IN NE. SIDE P.P. = S40°E 44.69'
N & W IN SE. SIDE A.P. = S52°W 28.57'
N & W IN NW. SIDE 32" OAK = N45°E 115.13'



LIBER 4 PAGE 249

Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date SEPTEMBER 11, 1996