

8888

NOV 0 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 5 PAGE 29

For corners in  
ST. JOSEPH

Located In: Corner Code #

(County)			
FABIUS TWP.			
1. Public Land Survey	T 6S R 12W	G-8	
	T R		
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

9 OCT 97 12:34 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on AUGUST 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

<u>1864 SURVEY IN A/78</u>	<u>1965 BY ROAD COMM</u>	<u>1976 SURVEY &amp; LCRC (3/83)</u>
STONE	8" SYCAMORE = N51°W 59.43'	FD 1/2" PIPE IN MON BOX
15" W.O. = S77°W 18 LKS	6" SILLOW = N25°W 47.85'	TELE POLE = N29°E 35.07'
	NW COR BARN = S71°E 152.82'	A.P. = SOUTH 33'
<u>1874 SURVEY IN A/204</u>	13" HEDGE = S1°E 67.77'	COR IS 1' NORTH OF CL ASPHALT
STONE FROM ORIGINAL BEARINGS	1/2" PIPE THRU WOOD STAKE	


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 36" PIPE IN MONUMENT BOX IN FILL AREA  
DUG 50" DEEP - NO ADDITIONAL EVIDENCE  
PIPE IS 1.3' NORTH OF CENTERLINE ASPHALT  
NW COR BARN = S71°E 151.90'  
13" HEDGE = S 1°E 67.05'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON AUG. 11, 1997  
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED PIPE WITH 5/8" X 24" BAR W/STD. CAP IN MON. BOX  
N & W IN E. SIDE A.P. = SOUTH 33.22'  
N & W IN E. SIDE MULBERRY = SOUTH 66.88'  
NW COR. FARM BLDG. = S72°E 151.89'  
SW COR. CHURCH FDTN. @ ENTRY = N71°W 312.99'  
3/4" PIPE = N45°W 26.96'



Signed by WAYNE A. MOSTROM  
Surveyor's Michigan License No. 14100

Date AUGUST 7, 1997