

FILED

JUN 27 12 47 PM '94

004 PG 039

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Cynthia A. Jewett
REGISTER OF DEEDS
ST. JOSEPH COUNTY

For corners in

ST. JOSEPH
(County)

Located In:

Corner Code *77*

SHERMAN TOWNSHIP

1. Public Land Survey	T <u>7 S</u> R <u>10 W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WAYNE A. MOSTROM, in a field survey on JULY 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5 GLO

L.C.R.C. - 1975 BY SAYERS

10" W.O. = S53°E 49 LKS.
24" W.O. = N46½°W 110 LKS.

P.P. = N70°W 63.60'
P.P. = S65°E 57.07'
P.P. = S64°E 58.2'

1880 SURVEY BY TODD (A/389)

IN REMAINS OF ORIG. STAKE FD. 8" HICK. = S10°W 85 LKS.
SET A CHERRY STAKE & OVER IT A STONE 12" HICK. = N5°W 1.245 CH.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 FOUND +1'D STONE OVER REMAINS OF OLD STAKE
RR SPIKE USED IN RECENT YEARS IS 1.57' SE'LY - NOTHING FOUND UNDER SPIKE

**SURVEY &
REMONUMENTATION**

AUG 31 1994

COMMISSION

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON 8/9, 1993
W.A. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 CORNER COMMON TO SEC'S 8, 9, 16, 17

SET 5/8" X 20" BAR IN MON. BOX
N & W IN W. SIDE 28" HICK. = N18°W 68.21'
N & W IN W. SIDE 40" OAK = N30°E
N & W IN SE SIDE P. POLE = N62°E 60.07'
RR SPIKE FD. (ERRONEOUS CORNER USED FOR 30+ YEARS) = S51°E 1.57'
N & W IN E. SIDE P. POLE = S21°E 77.50'
COR. IS 2.5' N. & 1' W. OF ∇ RDWY'S



Signed by *Wayne A. Mostrom*

Date 6/6/94

Surveyor's Michigan License No. 14100

REMONUMENTATION