

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

LIBER 4 PAGE 148

For corners in ST. JOSEPH Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

- 1. Public Land Survey T 7 S R 10 W G-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED  
19 MAY 95 2:32 P.M.  
CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on MAY, 1995, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO - POST  
LCRC 3, P. 107 PIPE IN MON BOX  
LCRC 3, P. 110 PIPE IN MON BOX  
VARIOUS SURVEYS BY SAYERS AND MOSTROM USED PIPE IN BOX  
REC. TIES A.P. EAST 32.67FT, A.P. WEST 28.35 FT, 6" DBL CEDAR SW 53.5 FT

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON may 8, 1995  
W. W. W. CO. REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" I.D. PIPE X 29" IN MON BOX. REMOVED PIPE AND BOX. FOUND POINTED STONE DOWN 3.2 FT BELOW PIPE. PEER GROUP ACCEPTED STONE AS TRUE CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" IRON X 24" AND ALUMINUM CAP OVER POINTED STONE  
WITNESS: A.P. WEST 28.85 FT, A.P. EAST 33.07 FT, TWIN 18" WALNUT S75°W 37.91 FT, 12" DBL CEDAR S35°W 53.48 FT.

Signed by Donald C. Andrews Date May 16, 1995  
Donald C. Andrews, P.S.  
Surveyor's Michigan License No. 33967

REMONUMENTATION

LIBER 4 PAGE 148

5/17/95