

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 4 PAGE 150

For corners in
St. Joseph Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 7 S R 10 W G-5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED
 19 MAY 95 2:33 P.M.
 CYNTHIA JARRATT
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on MAY, 1995, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - POST
 LCRC 3, 110 1975 IRON IN MON BOX
 SEVERAL SURVEYS BY SAYERS SHOW IRON IN MON BOX, AND NOTES FROM SAYERS SHOWS THAT R.E. SAYERS SET IRON IN MON BOX ON SURVEY
 SURVEY BY MOSTROM IN 1994 SHOWS 3/4" PIPE IN MON BOX
 LCRC 2, P. 290 1989 SHOWS PIPE IN MON BOX
 SURVEYOR'S RECORD A, P. 700 SHOWS SOMETHING EXIST BUT NO DESCRIPTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" I.D. PIPE X 17" IN MON BOX. REMOVED PIPE AND MON BOX. FOUND OLD TAR ROAD DOWN 4FT. AT 4.7 FT FOUND ANOTHER TAR ROAD. THE PEER GROUP DETERMINED NOT TO EXCAVATE WITH BACK HOLE TO LOOK FOR THE POSSIBLE CORNER BECAUSE OF THE SIZE OF AREA OF THE ROAD THAT WOULD HAVE TO BE REMOVED AND THEN BE REPAIRED. THERE FORE THEY ACCEPTED THE EXISTING PIPE IN MON BOX AS THE CORNER.

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON May 8, 1995
Wau CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" IRON X 24" WITH ALUMINUM CAP IN MON BOX AT SAME LOCATION OF PIPE
 WITNESS: PWR POLE S45°W 41.39FT, PRW POLE N45°W 49.21FT, GUY POLE N45°E 45.60 FT, A.P. S45°E 44.87FT

Signed by Donald C. Andrews Date May 16, 1995
 Donald C. Andrews, P.S.

Surveyor's Michigan License No. 33967