

**SURVEY &  
REMONUMENTATION**

JAN 22 1999

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1971**

**SECTION**

For Corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>10W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**LIBER 5 PAGE 118**  
STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

15 DEC 1998 11:19:02 AM

CYNTHIA L. JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

I, DONALD C. ANDREWS, in a field survey on JUNE 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.**

A. Description of original monument and accessories and/or Subsequent restoration:

GLO POST BEARING TREES LOCATED IN R/W  
CO. RD COMMISSION - NO DATE AND NO DESCRIPTION WIT.  
20" OAK N 2°E 70.2'R

SAYERS RECORDS SHOWS TIE TO PP NE 63.5'R  
MOSTROM'S RECORDS SHOWS FOUND IRON 1/2" DIA. IRON (6" DEEP), AND ALSO SHOWS IRON 1334.90' EAST OF (I-7).

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON DOWN 6" AND ALSO FOUND IRON WITH BROKEN CAP ALMOST MIDWAY BETWEEN (I-7) & (J-7) PER RECORD OF MOSTROM AND CHECKED WITH MOSTROM'S DISTANCE OF 1334.90' EAST OF (I-7)

FOUND PP N70°E 63.66'

FOUND 24" OAK NORTH 60.50'M



C: Description of monument for corner and accessories to perpetuate locating the position of the corner:

SET 5/8" IRON X 24 INCHES WITH STANDARD REMON. CAP IN MON. BOX ±3' N'LY OF CENTERLINE OF ROAD.

PP N 70°E 63.66'  
8" POPULAR N 40°E 38.11'  
24" OAK NORTH 60.50'  
5" POPULAR S 15°E 46.55'

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON June 8, 1998  
Wren CO. REPRESENTATIVE

Signed by Donald Andrews Date 10/28/98

Surveyors Michigan License No. 33967

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995  
ADAPTED FOR WORD PROCESSING

**REMONUMENTATION**

LIBER 5 PAGE 118