

FILED

JUN 27 12 47 PM '94

004 PG 042

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Cynthia R. J. ...
REGISTER OF DEEDS
ST. JOSEPH COUNTY

For corners in

ST. JOSEPH
(County)

Located In: Corner Code //

SHERMAN TOWNSHIP

- 1. Public Land Survey T 7S R 10W J-11
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **DAVID W. MOSTROM** in a field survey on **MAY 17, 1994** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-11) NORTH 1/4 COR. SEC. 35 T7S, R10W

GLO

W. OAK 22 NORTH 3.00
W. OAK 14 S 5 3/4 W 2.19

SURVEY BOOK A, PG 320

EVIDENTLY FOUND THE ORIGINAL POST - NO WITNESSESS GIVEN

SURVEY NO. S-12624 BY RLS NO. 33967

SET BAR & CAP MIDWAY & ON LINE BETWEEN SECTION CORNERS

6" TWIN MAPLE = N25°W 19.34'
3" MAPLE = N20°W 7.25'

5" CLUMP MAPLE = N48°E 8.38'
4" TWIN MAPLE = S45°W 17.43'

CORNER RECORDATION BOOK, PG. 209

SAME WITNESSESS AS SURVEY NO. S-12624

CORNER RECORDATION BOOK 3, PG 231

FOUND CONC. MONUMENT SAME WITNESSESS AS SURVEY NO. S-12624

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-11)

FOUND 2' LONG ORIGINAL WOOD POST BETWEEN 2 OLD ANCHOR POSTS IN MARSH. POST FALLS 1.5' WEST OF OLD FENCELINE RUNNING SOUTH AND FALLS IN E-W FENCELINE REMAINS. ALSO FOUND STAKE 22.77' EAST OF POST AS SET IN SURVEY IN BOOK A, PG 320 WHEN THE N-S 1/4 LINE WAS RUN. POST FOUND IS N54°W 15.3 FROM THE CONC. MONUMENT RECORDED IN BOOK 3, PG. 231.

SURVEY & REMONUMENTATION

AUG 31 1994

COMMISSION

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON *NOV. 8*, 1993
CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-11)

PLACED STANDARD CAP ON 5/8" X 80" REBAR INSIDE 1 3/4" X 5' LONG PIPE OVER ORIGINAL POST FOUND IN MARSH

PK & SHINER 2' HIGH IN W. SIDE OF 12" MAPLE = N24°E 8.34'
PK & SHINER 3' HIGH IN N. SIDE OF MAPLE CLUSTER = S78°E 17.56'
CONC. MONUMENT = S54°E 15.30'
PK & SHINER 3' HIGH IN W. SIDE OF 8" MAPLE = S18°E 61.60'
PK & SHINER 2.5' HIGH IN S. SIDE OF 6" MAPLE CLUSTER = S87°W 51.00'

Signed by *David W. Mostrom* **DAVID W. MOSTROM** Date **MAY 20, 1994**

Surveyor's Michigan License No. **32339**



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS AND MAPPING, 1971
MAY 14, 1975
REVISED JAN., 1983

REMONUMENTATION