

SURVEY & REMONUMENTATION

SEP 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 336

For corners in

<u>ST. JOSEPH</u>	Located in:	Corner Code #	
(County)			
FLORENCE TWP.			
1. Public Land Survey	T <u>75</u> R <u>11W</u>	<u>C-9</u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

18 APR 97 4:57 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on APRIL 7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>1890 SURVEY IN A/647</u>	<u>1950'S BY ROAD COMM.</u>	<u>SAYER'S 1972 SURVEY</u>	<u>1976 LCRC IN 3/127 AND SAYERS 1977 & 19 SURVEYS</u>
STONE SET BY MCLAUGHLIN 8" B.O.=S41 $\frac{1}{4}$ °E 70.5 LKS	STONE +D/MON BOX (NO WITNESS)	+D STONE 3" DEEP T.P.=SW 55.8' T.P.=SE 46' T.P.=NE 47.7'	P.P.=SW 55.8' POST=SE 46.0' MOSTROM 1996 SURVEY 3/4" PIPE IN MON BOX P.P.=S40°W 58.5' CL RDWY=EAST 1.60' 6" OAK=S70°W 60.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE OVER +D STONE IN MON BOX
CL RDWY TO N = WEST 3'
CL RDWY TO S = WEST 5'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON April 14, 1997
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 15" BAR IN CONC. OVER +D STONE IN MON. BOX
N & W IN SE SIDE P.P. = S40°W 58.50'
N & W IN NW SIDE 6" OAK = S70°W 60.50'
N & W IN SW COR. RR TIE A.P. = N25°E 81.90'
N & W IN SE COR. RR TIE A.P. = N75°E 85.54'
CL RDWY = EAST 1.6'



LIBER 4 PAGE 336

Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date 4/18/97