

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH (County)	Located In:	Corner Code #
FLORENCE TWP.	T <u>7S</u> R <u>11W</u>	<u>E-6</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 4 PAGE 317

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

17 MAR 97 9:37 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID W. MOSTROM, in a field survey on FEB. 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17	●	16				15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:


(E-6) 1/4 CORNER COMMON TO SECTIONS 16 & 17 T7S, R11W

GLO	1963 ROAD COMMISSION	1990 LCRC IN BK 2, PG 274
8" BURR OAK = S18°W 34.32'	STONE IN MON. BOX	FOUND 1/2" PIPE IN MON. BOX
8" BURR OAK = N10°E 14.52'	35" WHITE OAK = N20°W 71.2'	NE COR. SEC. N 2657.90'
	20" BLACK OAK = N45°E 50.2'	SE COR. SEC. S 2654.84'
	36" BURR OAK = S61°E 40.6'	
	24" WHITE OAK = S46°W 30.75'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-6)

FOUND 3/4"X11" PIPE OVER STONE 14" DEEP IN MON. BOX
CORNER FALLS IN CL OF SEVISON RD.
ALL 1963 ROAD COMM. WITNESSES ARE GONE
CORNER FALLS 3'± SOUTH OF TREELINE PROJ. TO EAST (600'±)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-6) 1/4 CORNER COMMON TO SECTIONS 16 & 17 T7S, R11W

SET 5/8"X10" IRON BAR W/STD. CAP IN CONC. OVER STONE IN MON. BOX
N&W IN E. SIDE OF 38" OAK = S18°W 111.58'
N&W IN NE. SIDE OF P. POLE = S40°E 44.81'
N&W IN E. SIDE OF 33' OAK = N05°W 252.10'
N&W IN W. SIDE OF P. POLE = N10°E 270.02'
3/4" PIPE = WEST 25.90'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON MARCH 10, 1997
Allen CO. REPRESENTATIVE

Signed by J. DW Mostrom DAVID W. MOSTROM
Surveyor's Michigan License No. 32339

Date MARCH 12, 1997

LIBER 4 PAGE 317