

**SURVEY &  
REMONUMENTATION**

SEP 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIBER 4 PAGE 335

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
FLORENCE TWP.		
1. Public Land Survey	T <u>7S</u> R <u>11W</u>	<u>E-11</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

18 APR 97 4:57 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on MARCH 27, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1889 SURVEY IN A/591  
SET STAKE IN REMAINS OF ORIGINAL POST & OVER IT A STONE  
20" W.O. = S45 3/4°W 68 LKS

1894 SURVEY IN A/659  
SURVEYOR USED CORNER BUT MADE NO REFERENCES MEASURED 40.15 CH. TO N 1/4 COR. SEC. 33

1966 BY ROAD COMMISSION  
LONG POINTED STONE & REMAINS OF WOOD STAKE  
P.P. = N30°W 75.3'  
WOOD A.P. = S50°E 35.50'  
TWIN TREE = N71°E 68.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 32" PIPE IN MON. BOX OVER POINTED STONE 36" DEEP ROAD HAS 2 1/2' FILL ± AT THIS POINT COR. IS IN Q STEARS RD. & 1' EAST OF STEARS RD. (PAVED)  
WOOD A.P. = S50°E 35.5'  
COR. WAS USED BY SAYERS IN 1970 (NO REF.'S)

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON April 14, 1997  
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 24" BAR W/STD. CAP OVER STONE IN MON. BOX  
3/4" PIPE = S55°W 40.24'  
N & W IN E. SIDE P.P. = N25°W 73.73'  
N & W IN W. SIDE BRACE POLE = N25°E 76.72'  
N & W NW SIDE 10" POPLAR = N50°E 39.66'  
N & W S. SIDE 28" OAK = S70°E 73.78'  
N & W IN N. SIDE 8" OAK = S40°E 48.14'



LIBER 4 PAGE 335

Signed by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date 4/17/97