

# SURVEY & REMONUMENTATION

SEP 12 1997

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 333

For corners in

|                                    |             |               |
|------------------------------------|-------------|---------------|
| ST. JOSEPH<br>(County)             | Located In: | Corner Code # |
| FLORENCE TWP.                      |             |               |
| 1. Public Land Survey              | T 7S R 11W  | E-13          |
|                                    | T R         |               |
|                                    | T R         |               |
|                                    | T R         |               |
| 2. Property Controlling in Section | S T R       |               |
|                                    | S T R       |               |
| 3. Miscellaneous Property in Sec.  | S T R       |               |
|                                    | S T R       |               |

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

18 APR 97 4:57 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on MARCH 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| 1  | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

|   |   |  |   |
|---|---|--|---|
| 1889 SURVEY IN A/591<br>STONE SET BY FORMER SURVEYOR FROM ORIG. BEARING TREES | 1963 ROAD COMMISSION<br>STONE WITH BRICK UNDER MON. BOX<br>A.P. = N48°E 43.0'<br>P.P. = N30°W 45.3'<br>A.P. = S40°W 35.7' | 1977 SAYERS SURVEY<br>PIPE IN MON. BOX<br>P.P. = S45°E 46.3'<br>P.P. = N45°E 46.6'<br>A.P. = N45°W 41.1' | NOTE: THIS IS A COMMON CORNER WITH E-1 OF T8S, R11W |
|---|---|--|---|

NO WITNESSES  
MEASUREMENT TO W 1/4 COR. = 40.23 CHAINS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 3/4" X 18" PIPE OVER POINTED STONE  
22" DEEP IN MON. BOX  
IN C OF ROAD INTERSECTION  
P.P. = S45°E 46.3'

NOTE: THIS IS A COMMON CORNER WITH E-1 OF T8S, R11W

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON April 14, 1997  
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 17" BAR W/STD. CAP OVER STONE IN MON. BOX  
SE COR. BRICK HSE = N65°W 163.87'  
N & W IN W. SIDE P.P. = N33°E 71.03'  
N & W IN NE SIDE P.P. = S40°E 46.65'  
N & W IN SW SIDE P.P. = S15°E 101.91'  
3/4" PIPE = S45°W 36.88'  
CORNER IS COMMON WITH E-1 OF T8S, R11W



Signed by Wayne A. Mostrom  
Surveyor's Michigan License No. 14100

Date 4/17/97