

OCT 01 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ST. JOSEPH</u>	Located In:	Corner Code #
<u>FLORENCE TWP.</u>		
1. Public Land Survey	T <u>7S</u> R <u>11W</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 4 PAGE 321

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

17 MAR 97 9:43 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID W. MOSTROM, in a field survey on FEB. 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5							●						
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G-5) CORNER COMMON TO SECTIONS 9, 10, 15 & 16 T7S, R11W		
GLO	1960'S ROAD COMMISSION	1984 SURVEY BY SAYERS
9" HICKORY = SOUTH 4.62'	STONE IN MON. BOX	3/4" PIPE IN MON. BOX
7" BURR OAK = N17°W 21.78'	ANCHOR POST = N43°E 41.50'	FENCE CORNER = N45°E 41.82'
	NW GRAVE MARKER (CALHOUN) = S47°E 66.31'	NE COR. FNDTN. = S40°W 106.45'
	BRICK BLDG. = S50°W 106.20'	SW COR. CALHOUN MARKER = S45°E 68.2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-5)
 FOUND 3/4"X9" PIPE OVER STONE 10" DEEP
 ANCHOR POST = N43°E 41.7' TO FACE
 NW COR. CALHOUN GRAVE STONE = S47°E 66.31'
 BRICK BLDG. = S50°W 106.20' (FNDTN.)
 SW COR. CALHOUN GRAVE MARKER = S45°E 68.2'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON 3/10/97, 1997
CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-5) CORNER COMMON TO SECTIONS 9, 10, 15 & 16 T7S, R11W
 SET 5/8"X7" IRON BAR W/STD. CAP IN CONC. OVER STONE IN MON. BOX
 NE COR. BRICK CHURCH = S50°W 106.41'
 NW COR. CALHOUN GRAVE STONE = S47°E 66.36'
 N&W IN W. SIDE OF ANCHOR POST = N43°E 41.95'
 N&W IN W. SIDE OF 33" OAK = N35°E 72.79'
 N&W IN N. SIDE OF 32" MAPLE = S62°E 66.25'



Signed by David W. Mostrom DAVID W. MOSTROM

Date MARCH 12, 1997

Surveyor's Michigan License No. 32339

PAGE 321