

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>St. Joseph</u> <small>(County)</small>	Located In:	Corner Code: <u>##</u>
1. Public Land Survey	T 7S R 12W	A-6, A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Donald L. Bissell in a field survey on October, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 W 1/4 Cor. Sec. 18	A-7 SW Cor. Sec. 18
Set 4" x 36" Conc. Mon. w/Alum.	Found 1/2" Rod Beside 1" Flat Iron
Cap Halfway Between NW Cor. and SW Cor. of Sec. 18	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 W 1/4 Cor. Sec. 18	A-7 SW Cor. Sec. 18
4" x 36" Conc. Mon.	1/2" Rod
N45°E - 30.74' - 12" Maple	N29°E - 65.47' - 10" Ash
N82°E - 2.18' - 10" Swamp Oak	N74°E - 34.76' - 14" Bass Wood
S45°E - 26.33' - 6" Maple	N82°W - 25.48' - Power Pole
N10°W - 49.00' - 10" Maple	East - 3' - Center Road
North - 33.87' - Conc. Mon.	Spike and tag in Trees and P.P.
North - 94.89' - Conc. Mon.	
E 1/4 Cor. Sec. 13, T7S, R13W	
Spike and Tag in Trees	

Signed by Donald L. Bissell Date _____
 Surveyor's Michigan License No. 18655

