

**SURVEY & REMONUMENTATION**

**JUL 16 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE** LIBER 5 PAGE 67  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

11 JUN 1998 9:50:14 AM

CYNTHIA L. JARRATT  
 REGISTER OF DEEDS

For corners in

<u>ST. JOSEPH</u>	Located In:	Corner Code #
(County)		
CONSTANTINE TWP.	T 7S R 12W	C-7
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on 5/26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1898 SURVEY IN A/807	F. LABAR'S DATA @ ROAD COMM. - 1981	1981 LCRC IN 2/148
COR. IS LOST - NO WIT. FOUND SET OAK STAKE FROM SOUTH	½" BAR OVER OAK STAKE	½" IRON OVER STAKE
5" CHERRY = S12°25'E 77½ LKS	6" CHERRY = N45°W 2.67'	SAME WIT. AS 1981 WORK
(COR. IS 39.96 CH. W. OF S¼	10" BURR O. = S85°E 20.0'	1984 & 1987 SURVEY BY MOSTROM
COR. SEC. 17 & 40.05 CH. E.	10" W.O. = S85°W 17.14'	SAME WIT. AS 1981 WORK
OF S¼ COR. SEC. 18)		"CAPPED IRON FOUND"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON CAPPED #27451 - NOTHING BELOW IT  
 ALL OF 1981 WIT'S ARE IN AND CHECK O.K.  
 COR. FALLS IN LINE W/FENCE TO EAST

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON JUNE 8, 1998  
W.A.M. CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 48" IRON BAR WITH STD. CAP IN PLACE OF IRON FOUND  
 N & W IN N. SIDE 16" OAK = S85°W 17.50'  
 N & W IN NE SIDE 10" CHERRY = N45°W 2.67'  
 N & W IN S. SIDE 16" W.O. = S85°E 20.37'  
 N & W IN N. SIDE GATEPOST = EAST 18.67'  
 N & W IN SE SIDE 5" ELM = N45°E 4.09'



LIBER 5 PAGE 67

Signed by Wayne A. Mostrom WAYNE A. MOSTROM Date JUNE 9, 1998  
 Surveyor's Michigan License No. 14100