

**SURVEY & REMONUMENTATION**

**JUL 16 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE** **LIBER 5** **PAGE 81**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH

Located In:

Corner Code #

(County)

CONSTANTINE TWP.

1. Public Land Survey

T 7 S R 12 W E-12

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

26 JUN 1998 4:36:30 PM

CYNTHIA L. JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

DAVID W. MOSTROM, in a field survey on MAY 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- \* GLO 10" W. OAK=N31°E 26.4'
- 14" W. OAK=N50°E 23.1'
- \* 1959 ROAD COMMISSION WOOD STAKE OVER STONE SURROUNDED BY METAL 15" OAK=S50°W 39.7'
- 12" HICKORY=S75°W 40.4'
- 15" HICKORY=N50°W 67.3'
- \* 1995 LCRC IN L-4, P-177 SET 5/8" X 24" IRON BAR IN PLACE OF + 'D STONE FOUND 16" OAK=N45°E 29.91'
- 24" HICKORY STUMP=N50°W 67.3'
- 16" HICKORY=S75°W 40.4'
- 18" OAK=S15°W 155.05'
- 24" OAK=S05°W 38.03'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON BAR AS SET ON LCRC IN L-4, P-177  
 18" HICKORY=S75°W 40.4'  
 26" STUMP=N50°W 67.3'

ALL WITNESSES SHOWN ON LCRC IN L-4, P-177 ARE IN AND OK

CORNER FALLS IN N-S FENCELINE  
 PLACED STANDARD REMON. CAP ON IRON

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON May 11, 1998  
Wiley CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5/8" X 24" IRON BAR W/STD. CAP
- N & W 2.5' HIGH ON NW SIDE OF 18" OAK=N45°E 29.91'
- " N. SIDE OF 18" HICKORY=S75°W 40.40'
- N & W 2.0' HIGH ON E. SIDE OF 28" OAK=S05°W 39.70'
- " NE SIDE OF 10" OAK=S40°E 38.03'
- " N. SIDE OF 10" CHERRY=N60°W 25.64'



Signed by J. W. Mostrom DAVID W. MOSTROM Date MAY 12, 1998  
 Surveyor's Michigan License No. 32339