

NOV 04 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH

(County)

CONSTANTINE TWP.
1. Public Land Survey

Located In:

Corner Code #

Table with 3 columns: Township/Range, Section, and Corner Code. Row 1: T7S R12W I-4. Row 2: T R. Row 3: T R. Row 4: T R. Row 5: S T R. Row 6: S T R. Row 7: S T R. Row 8: S T R.

LIBER 5 PAGE 33

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

22 OCT 97 11:38 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, WAYNE A. MOSTROM, in a field survey on OCT. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Cell (4,10) contains a circled cross symbol.

A. Description of original monument and accessories and/or subsequent restoration:

3LO POST LCRC IN L-2, P-90 & SAYERS 1977 SURVEY LCRC IN L-2, P-227 3/4" PIPE IN MON. BOX 1988 MOSTROM SURVEY SAME DATA AS L-2, P-227
15" W.O.=N54°W 59 LKS
19" W.O.=S31°E 22 LKS
A.P.=WEST 32.8'
RR TIE=S38°W 39.0'
COR. IS IN Q RD. & IN LINE W/FENCES
10" CHERRY=N16°W 111.0' RR TIE=S56°W 48.57'
EDGE=S89°E 30.0'
A.P.=WEST 32.45'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 36" PIPE IN MON. BOX
A.P. = WEST 32.8' (FACE OF POST)
P.P.=N65°E 39.88'
COR. IS IN FENCELINES & 1.5' E. OF Q ASPHALT

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Oct. 13, 1997
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED PIPE FOUND WITH 5/8" X 24" BAR W/STD. CAP IN MON. BOX
N & W IN S. SIDE 10" A.P. = WEST 33.30'
N & W IN NW SIDE P.P. = N65°E 39.88'
N & W IN N. SIDE 14" LOCUST = EAST 47.35'
N & W IN E. SIDE P.P. = S12°W 187.17'



LIBER 5 PAGE 33

Signed by [Signature]
Surveyor's Michigan License No. 14100

Date 10/14/97