

**SURVEY & REMONUMENTATION**

**JUL 16 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**LIBER 5 PAGE 82**

For corners in

ST. JOSEPH

Located In:

Corner Code #

(County)

CONSTANTINE TWP.

1. Public Land Survey

T 7S R 12W

J-13

T 8S R 12W

J-01

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

26 JUN 1998 4:36:48 PM

CYNTHIA L. JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID W. MOSTROM, in a field survey on MAY, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
1897 SURVEY IN BK. A, PG. 745 \*1916 SURVEY IN BK. B, PG. 498 \*1978 SAYERS SURVEY  
SET OAK POST IN PLACE OF GAS PIPE ON LINE MID-WAY BETWEEN SECTION CORNERS FOUND 1/2" PIPE IN MON. BOX  
DECAYED STAKE RAIL FENCE=SOUTH 33' \*1964 ROAD COMMISSION POINTED STONE IN MON. BOX CONC. POST=NW 13.60'  
P. POLE=N66°W 36.50' CONC. POST=SW 48'  
ANCHOR POST=N09°W 13.50' \*1992 MOSTROM SURVEY FOUND 3/4" PIPE IN MON. BOX  
CONC. ANCHOR POST= SOUTH 28.10' (FACE) NE COR. CONC. POST= S02°E 28.03'  
P. POLE=N02°W 30.24'  
3/4" PIPE=N45°E 29.65'  
3/4" PIPE=S45°W 24.81'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 3/4" X 26" (OD) PIPE OVER POINTED STONE IN MON. BOX  
CENTERLINE DICKENSON ROAD=SOUTH 0.7'  
FENCELINE PROJECTS TO NORTH & SOUTH=WEST 1.5'  
NE COR. CONC. ANCHOR POST=S02°E 28.08'  
P. POLE=N02°W 30.18'  
1" (OD) PIPE=N45°E 29.65'  
1" (OD) PIPE=S45°W 24.81'  
SET 5/8" X 24" IRON BAR W/STD. CAP IN PLACE OF PIPE

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON May 11, 1998  
Warr CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
5/8" X 24" IRON BAR W/STD. CAP IN MON. BOX  
N & W 1.0' HIGH ON E. SIDE OF P. POLE=N02°W 30.04'  
NE COR. 3' X 3' CONC. MONUMENT POST=S02°E 28.08'  
N & W IN N. SIDE OF P. POLE=S78°W 151.03'  
1" OD PIPE IN DITCH=N45°E 29.65'  
1" OD PIPE IN DITCH=S45°W 24.81'  
1" OD PIPE IN DITCH=S45°E 25.00'



NOTE: THIS IS A COMMON CORNER WITH (J-1) T8S, R12W

Signed by J.W.M. DAVID W. MOSTROM Date MAY 12, 1998

Surveyor's Michigan License No. 32339

**REMONUMENTATION**