

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1971

For Corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>9W</u>	<u>C-9</u>
	T _____ R _____	SURVEY &
	T _____ R _____	REMONUMENTATION
	T _____ R _____	JAN 31 2001
2. Property Controlling	S _____ T _____ R _____	SECTION
in Section	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	
Property in Sec.	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 6 PAGE 42
 STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED
 6 JUN 2000 10:13:57 AM
 CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DONALD C. ANDREWS, in a field survey on APRIL 18, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.

A. Description of original monument and accessories and/or Subsequent restoration:

GLO POST 14" W. OAK S64°W 36.96', 6" HICKORY S53°E 45.54'

1978 SAYERS SURVEY A.P. N46°W 43.55', A.P. S45°20'E 47.3', A.P. N48°E 44.6'

1864 GARDNER BK. A PG. 80 STONE FROM BEARING TREE

LCRC 2 PAGE 218 DATED 11/2/88 ¾" PIPE ON MON BOX, P.P. N28°W 62.3', A.P. N48°E 44.7', A.P. S45°E 47.7'

1963 CO ROAD NO DESCRIPTION NO DATE A.P. N45°W 43.1', A.P. N47°E 43.0', PUMP S42°E 104.6'

1999 MOSTROM SURVEY FOUND ¾" PIPE IN MON BOX WITS. SAME AS LCRC DATED 11/2/88

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RECORD ¾" X 12" PIPE OVER POINTED STONE DOWN 1.5'
 U.P. N18°W 62.13'M
 A.P. N45°E 44.66'M
 A.P. S45°E 47.72'M

LOCATED IN CENTERLINE OF KELLY AND BIG HILL ROAD
 THE CORNER IS IN THE INTERSECTION OF ROADS N-S & E-W

C: Description of monument for corner and accessories to perpetuate locating the position of the corner:

SET CAPPED 5/8"X8" IRON IN CONCRETE IN MON BOX
 U.P. N18°W 62.13'M
 A.P. N45°E 44.66'M
 A.P. S45°E 47.72'M
 FNC POST S70°E 68.91'M

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON April 10, 2000
 _____ CO. REPRESENTATIVE



Signed by Donald Andrews Date 4-19-00

Surveyors Michigan License No. 33967

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995
 ADAPTED FOR WORD PROCESSING

REMONUMENTATION