

SURVEY & REMONUMENTATION

MAY 05 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 126

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

12 APR 95 3:16 P.M.

CYNTHIA JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code \neq #
<u>BURR OAK TWP.</u>		
1. Public Land Survey	T <u>7S</u> R <u>9W</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DAVID W. MOSTROM, in a field survey on MARCH 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(D-5) SOUTH 1/4 COR. SEC. 8

GLO 1870 SURVEY IN BOOK A, PG. 168
 14" TAMARAC = S45°E 17.16' STAKE SET FROM ORIG. BRG. STUMPS
 10" TAMARAC = N39 2/3°W 9.24' NO WITNESSES GIVEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D-5)

FOUND POINTED OAK STAKE 14" LONG ON SOUTH SIDE OF REMAINS OF OLD ANCHOR POST, IN BOTTOMLAND.
 STAKE FALLS IN NORTH-SOUTH FENCE AND IN REMAINS OF FENCE RUNNING EAST.

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON April 10, 1995
W. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D-5) SOUTH 1/4 COR. SEC. 8

SET 5/8" X 24" IRON BAR W/STD CAP IN STAKE 0.5' SOUTH OF REMAINS OF ANCHOR POST
 N & W 1.5' HIGH IN NE SIDE OF 8" TAMARAC = N39 1/2°W 10.37'
 N & W 2.0' HIGH IN S. SIDE OF 8" ELM = S67°W 18.05'
 N & W 2.0' HIGH IN N. SIDE OF 8" TAMARAC = N87°E 19.56'
 N & W 2.0' HIGH IN NW SIDE OF 8" TAMARAC = N30°E 28.57'

Signed by J. W. Mostrom

Date APRIL 11, 1995

Surveyor's Michigan License No. 32339

