

SURVEY & REMONUMENTATION
APR 10 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ST. JOSEPH (County)	Located In:	Corner Code --#
1. Public Land Survey	T <u>7S</u> R <u>9W</u>	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

6 DEC 94 4:31 P.M.

CYNTHIA JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WAYNE A. MOSTROM in a field survey on JULY 25, 1994
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4
GLO 1870 SURVEY BY GARDNER L.C.R.C.-L-2, P-27 (1975)
 12" Y.O. = S1°E 9.85 LKS SET STAKE IN MARSH SET 1/2" IRON BAR
 13" Y.O. = NORTH 10.38 LKS FROM ONE ORIGINAL BEARING TREE A.P. = N30°W 35.55'
 ST. SIGN = S45°E 38.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4
 FD. REMAINS OF OLD SHARPENED STAKE 4' DEEP AT MARSH LEVEL PER 1870 SURVEY ABOUT 1.3' NW OF IRON SET IN 1975 SET PROPORTIONALLY

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON August 8, 1994
W. A. Mostrom CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 (1/4 CORNER BETWEEN SEC'S 8 & 9)
 SET 5/8"X24" THROUGH OLD STK FD. @ MARSH LEVEL 48" DEEP
 ALSO SET 5/8"X24" BAR & STD. CAP OVER ABOVE POINTS & SET MON. BOX @ ROAD LEVEL
 CL N. END CULVERT = N50°W 45.83'
 5/8"X24" IRON BAR = N20°W 33.16'
 N & W IN S. SIDE 24" TREE = N70°W 105.95'
 N & W IN NE SIDE 12" ASH = S30°E 97.29'
 CL N-S RDW = E 10', COR IS IN CL E-W RDWY



Signed by Wayne A. Mostrom Date 9/25/94
 Surveyor's Michigan License No. 14100

REMONUMENTATION