

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1971

For Corners in

ST. JOSEPH Located In: Corner Code #
 (County)
 1. Public Land Survey T 7 R 9 G-7
 T ___ R ___
 T ___ R ___ **SURVEY &**
 T ___ R ___ **REMONUMENTATION**
 2. Property Controlling S ___ T ___ R ___ **JAN 31 2001**
 in Section S ___ T ___ R ___ **SECTION**
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

LIBER 6 PAGE 40
 STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED
 4 MAY 2000 10:07:18 AM
 CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DONALD C. ANDREWS, in a field survey on MARCH 7, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.

A. Description of original monument and accessories and/or Subsequent restoration:

CO. ROAD RECORDS 1963 LONG POINTED STONE UNDER MON. BOX
 AP N41°W 43.85', 20" OAK S58°W 51.1', 28" OAK S15°W 35.6'

LCRC 4 PAGE 162 STONE IN MON. BOX: 8/21/95
 30" OAK S10°W 35.60', 30" OAK S45°W 51.05'
 PP N50°E 48.95', PP N 30°E 75.08'

1994 MOSTROM SURVEY FND STONE IN MON. BOX WIT.:
 PP N30°E 75.05', PP N60°E 48.95'
 36" OAK S15°W 35.60', 28" OAK S58°W 51.60'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

ONE P.P. HAS BEEN REPLACED, DOES NOT MATCH RECORD
 LCRC DATED 8/21/95
 UP N56°E 48.97'
 30" OAK S10°W 35.52'
 30" OAK S50°W 51.03'

MON. BOX FELL IN CENTERLINE OF NEEDHAM AND 2' NORTH OF CENTERLINE MAYSTEAD.

**RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON MARCH 13, 2000
 WALKER CO. REPRESENTATIVE**

C: Description of monument for corner and accessories to perpetuate locating the position of the corner:

CAPPED IRON 5/8" X 3" IN CONCRETE IN MON. BOX
 PP N56°E 48.97'
 PP N28°E 73.32'
 30" OAK S10°W 35.52'
 30" OAK S50°W 51.03'

Signed by Donald Andrews Date 3-21-00

Surveyors Michigan License No. 33967



LIBER 6 PAGE 40

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995
 ADAPTED FOR WORD PROCESSING

REMONUMENTATION