

SEP 12 1997

COMMONWEALTH

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 330

For corners in St. Joseph Located in: Corner Code # (County)

- 1. Public Land Survey T 7S R 9W H-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN ST. JOSEPH COUNTY FILED

16 APR 97 4:44 P.M.

CYNTHIA JARRATT REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on March 11, 1997, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Post

LCRC 1, P 33 Boon 1974 Set 1/2" iron Pin 10 ft E. of centerline Co. Road as per section protraction procedures. fnc post S40°E 13.26', 10" oak N80°W 83.35'

LCRC 3, P 140 by Mostrom (no date) iron pipe same wit as Boone

Mostrom survey 1992 same wit as Boone plus 12" Walnut S62°W 76.18'

Various surveys by Boone, Sayers and Mostrom used this corner.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found capped iron in mon. box (capped smashed) check wit to fnc corn to the SE, oak to NW & Walnut to SW. All checked good with the witnesses.

RATIFIED BY PEER GROUP IN ACCORDANCE WITH P.A. 345 ON March 10, 1997 [Signature] CO. REPRESENTATIVE (This cor. is common with H-1 of T85, R9W)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set aluminum remon. cap on 5/8" x 24" iron in monument box: PP S75°E 17.76', 14" twin Walnut S55°E 75.71', 18" Oak N85°W 82.78', 18" Oak N55°W 61.41'



Signed by Donald C. Andrews, P.S. Surveyor's Michigan License No. 33967

Date 4/14/97

LIBER 4 PAGE 330