

**SURVEY & REMONUMENTATION**

SEP 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 328

For corners in \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 St. Joseph (County)

1. Public Land Survey T 7S R 9W I-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

16 APR 97 4:43 P.M.

CYNTHIA JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on March 11, 1997, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO post

LCRC 1, P 33 Boone found stone at field div. at ground surface

various surveys by Mostrom and Sayers shows stone. A Mostrom survey shows the H-1 of T8S,R9W and an iron midway with I-1 of T8S,R9W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

stone is gone and all witness to corner are gone. corner is now located in corn field. found H-1 and iron set mid way. Reestablished corner per previous Mostrom as best evidence of location of corner.

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345

ON March 10, 1997

Wesley CO. REPRESENTATIVE

(This corner is common with I-1 of T8S, R9W)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

set alumi remon. cap 5/8"x24" iron down 19" in corn field: set capped 1/2" iron x 18" down 12" in corn field for witnesses 1) N45° 31.80', 2) S45W 34.72', 3) S45°E 32.00', 4) N45°E 31.97



Signed by Donald C. Andrews  
 Donald C. Andrews, P.S.  
 Surveyor's Michigan License No. 33967

Date 4/14/97

REMONUMENTATION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

LIBER 4 PAGE 328