

**SURVEY &
REMONUMENTATION**

JAN 22 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1971

For Corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>9W</u>	<u>J-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 5 PAGE 112
STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

15 DEC 1998 11:16:20 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

I, DONALD C. ANDREWS, in a field survey on October 21, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.

A. Description of original monument and accessories and/or Subsequent restoration:

GLO POST BEARING TREES ARE GONE

LCRC ^A P. 202 ANDREWS FOUND "X" STONE WHERE THE FENCES WOULD INTERSECT IF THEY WERE EXTENDED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "X" STONE PER LCRC 4, P. 202, ALL WIT. CHECK GOOD

SEARCHED FOR POSSIBLE CORNER 21'-24' S'LY OF "+" STONE. DID NOT FIND ANY "+" STONE LIKE AT THE RECORDED CORNER, AND THE ACCEPTED CENTER OF SECTION 2. ACCEPTED AS BEST EVIDENCE BY PEER GROUP. WITNESSES SHOWN ON LCRC 2, P. 202 AGREE WITH DISTANCES AS MEASURED AND ARE SHOWN BELOW IN PART "C".

C: Description of monument for corner and accessories to perpetuate locating the position of the corner:

SET 5/8" IRON X 24 INCH IRON WITH STANDARD REMON. CAP IN PLACE OF LARGE "X"ed STONE

24" OAK EAST 7.63'
30" QUAD TREE S 5°E 14.00'
8 " HICKORY N 70°W 18.72'
50" OAK N 20°W 46.10'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON Oct. 12, 1998
W CO. REPRESENTATIVE



Signed by Donald C. Andrews Date 10/28/98

Surveyors Michigan License No. 33967

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVORS, JAN. 28, 1971

REMONUMENTATION

REVISÉD MAY 14, 1975
REVISÉD JAN., 1983
REVISÉD OCT., 1995
ADAPTED FOR WORD PROCESSING

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

LIBER 5 PAGE 112