

**SURVEY &
REMONUMENTATION**

JAN 22 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1971

For Corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>9W</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 5 PAGE 116

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

15 DEC 1998 11:18:10 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

I, DONALD C. ANDREWS, in a field survey on JUNE 3, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.

A. Description of original monument and accessories and/or Subsequent restoration:

GLO POST BEARING TREES ARE GONE
CO. SURVEYOR'S RECORD BOOK A, P. 158 GARDNER 1867 - NO DESCRIPTION OR WITNESS.
CO. SURVEYORS RECORD BOOK A, P. 178 ROSE 1871 - STAKE SET FROM STUMP OF THE OLD BEARING TREE
CO. ROAD COM. BRIDGE PLANS SHOWS CORNER IS 2637.40 FEET SOUTH FROM E1/4 CORNER OF SEC. 2 AND THE BRIDGE DECK IS CENTERED ON THE SECTION LINE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PK NAIL 2637.40 FEET SOUTH OF E1/4 CORNER OF SEC. 2 AND CENTERED ON BRIDGE DECK

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOND PK IN CENTERLINE OF CONCRETE BRIDGE DECK. THE BRIDGE DECK IS COVERED WITH A THIN LAYER OF SEAL COAT. LEFT PK AS FOUND. SET CAPPED IRONS FOR WITNESSES PER PEER GROUP.

SET CAPPED IRON N 35°E 19.82'
SET CAPPED IRON S 25°E 40.27'
SET CAPPED IRON S 25°W 40.44'
SET CAPPED IRON N 40°W 19.05'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON June 8, 1998
Wass CO. REPRESENTATIVE



Signed by Donald Andrews Date 10/28/98

Surveyors Michigan License No. 33967

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995
ADAPTED FOR WORD PROCESSING

REMONUMENTATION

LIBER 5 PAGE 116