

**SURVEY &
REMONUMENTATION**

JAN 22 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1971**

For Corners in

<u>St. Joseph</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>9W</u>	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

LIBER 5 PAGE 117

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

15 DEC 1998 11:18:34 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

I, Donald C. Andrews, in a field survey on October 6, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.

A. Description of original monument and accessories and/or Subsequent restoration:

Co. Road Com. 1962 Jones Stone and 1/2" pipe under mon. box.
29" Maple N42°W 47.0', SW Corner Barn N41°E 54.4' (Gone), 16"
Walnut S63°E 58.2'.

Sayers 1978 survey shows 3/4" pipe in mon box. 24" Walnut S65°E
57.58', SW Corner Barn N41°E 54.38' (gone), 30" Maple N41°W
46.93'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2"x14" pipe in mon box. Removed mon box and found
pointed stone below pipe down 21" below road surface. 34" Maple
N40°W 46.22', 31" Maple N30°W 74.55', 23" Walnut S60°E 57.69'

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:
SET 5/8" IRON WITH STANDARD REMON. CAP IN CONC. OVER
STONE IN MON. BOX AT THE INTERSECTION OF TWO ROADS

34" MAPLE N 40°W 46.22'
31" MAPLE N 30°W 74.55'
23" WALNUT S 60°E 57.69'
"+" TOP OF CULVERT (CMP) S 50°W 44.00'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON OCT. 12, 1998
Willis CO. REPRESENTATIVE



Signed by Donald Andrews Date 10/21/98

Surveyors Michigan License No. 33967

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995
ADAPTED FOR WORD PROCESSING

REMONUMENTATION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

LIBER 5 PAGE 117