

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1971

For Corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>9W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	SURVEY & REMONUMENTATION	
2. Property Controlling	S _____ T _____ R _____	<u>JAN 31 2001</u>
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	<u>SECTION</u>
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

LIBER 6 PAGE 63

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

11 AUG 2000 11:27:46 AM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DONALD C. ANDREWS, in a field survey on JUNE 30, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.

A. Description of original monument and accessories and/or Subsequent restoration:

- | | |
|--|---|
| GLO POST 9" WHITE OAK N40 1/3°E 26.4', 12" WHITE OAK N77°W 176.88' | 1984 MOSTROM SURVEY FOUND 3/4" IRON BAR IN MON BOX WIT'S 24" CHERRY S88°W 51.6', TELE. POLE N20°E 83.34', 18" WALNUT EAST 47.6' |
| BK. A PAGE 174 1871 ROSE COUNTY SURVEYOR STAKE SET BY OLD BEARING TREES IN ACCORDANCE WITH THE FIELD NOTES | 1994 MOSTROM SURVEY 3/4" BAR IN MON BOX WIT'S SAME AS 1984 SURVEY |
| BK. A PAGE 172 1871 ROSE COUNTY SURVEYOR STONE IN PLACE OF OLD STAKE, 32" W OAK N7°W 126.06' | 1997 MOSTROM SURVEY WIT'S SAME AS 1984 SURVEY |
| 1959 COUNTY ROAD COMMISSION STEEL ROD IN PLACE OF STONE MONUMENT BOX TELE POST EAST 31.0' | NO DATE SAYERS NOTES STEEL ROD IN PLACE OF LARGE STONE N MON BOX RD. COMM |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|--|
| FOUND RECORD 3/4" X 20" PIPE IN MON BOX
REMOVED BOX, FOUND SECOND BOX APPROX. 3' BELOW
FIRST BOX, DUG HOLE APPROX. 14" BELOW SECOND BOX.
FOUND NOTHING | LOCATED 2.5' WEST OF CENTERLINE OF BURR OAK ROAD
36" CHERRY WEST 51.68'
WALNUT STUMP EAST 47.65' |
|---|--|

C: Description of monument for corner and accessories to perpetuate locating the position of the corner:

SET 5/8" X 24" CAPPED IRON IN MON. BOX

- 36" CHERRY WEST 51.68'
- UP S40°W 86.71'
- 6" WALNUT N10°E 82.38'
- 10" TWIN MAPLE
- WALNUT STUMP EAST 47.65'

**RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON JULY 10, 2000
 Wagon CO. REPRESENTATIVE**



LIBER 6 PAGE 63

Signed by Donald Andrews Date 7-27-00

Surveyors Michigan License No. 33967

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995
 ADAPTED FOR WORD PROCESSING

REMONUMENTATION