

NOV 04 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 5 PAGE 24

For corners in

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
BURR OAK TWP. 1. Public Land Survey	T7S R9W	L-5
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

19 SEP 97 2:57 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on JULY 29, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO
24" Y.O. = S10 1/3°E 1.12 CH
30" Y.O. = N2°E .83 CH

ROAD COMMISSION RECORDS
CORNER IS CIRCLED IN INDEX
BOOK AS FOUND BUT NO REFERENCES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG 12' X 20' HOLE WITH MOTOR GRADES IN JOINT EFFORT WITH COUNTY ROAD COMMISSION.
FOUND RECTANGULAR SHAPED STONE 16" LINE IN UPRIGHT POSITION WITH A LID ONLY TO A MONUMENT BOX ON TOP OF IT.
CORNER IS IN FENCE TO SOUTH AND IN EAST-WEST CENTERLINE OF GRAVEL ROADWAY
CENTERLINE OF GRAVEL ROADWAY TO NORTH IS WEST 2' MORE OR LESS.

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON AUG. 11, 1997
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 24" BAR W/STD. CAP IN MON. BOX IN PLACE OF STONE
N & W IN SE SIDE 36" MAPLE=N36°E 37.08'
N & W IN E. SIDE 36" TR1-CHERRY=N10°W 99.88'
N & W IN S. SIDE TELE. POLE=N78°W 103.45'
NW COR. HOUSE=S49°W 103.23'



Signed by WAYNE A. MOSTROM
Surveyor's Michigan License No. 14100

Date SEPTEMBER 17, 1997

LIBER 5 PAGE 24