

SURVEY & REMONUMENTATION

FEB 08 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

St. Joseph

Located In:

Corner Code #

(County)
Fawn River Twp.
1. Public Land Survey

T	8S	R	9W	A-5
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

2. Property Controlling in Section
3. Miscellaneous Property in Sec.

LIBER 5 PAGE 168

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

7 JUN 1999 10:43:51 AM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David W. Mostrom, in a field survey on 5/4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A-5) NW Cor. Sec. 18 T8S, R9W

*1877 Survey in Bk A, Pg 262
Set stone 62 links (40.92') South of Sturgis Twp. Cor.
12" Aspen = S21°W 77.00'

*1960's Road Comm.
Stone under Mon. box
15" Hick.=S41°W 53.4'
20" Hick.=S28°W 74.4'
19" Oak =S27°E 70.1'

*1980 Sayers Survey
Found 3/4" pipe in Mon. box
P. Pole = N78°10'E 42.3'
P. Pole = N73°30'W 32.0'
C-C = North 38'±

*1996 Mostrom Survey
Found 1/2" pipe in Mon. box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 11" pipe over +d stone In Mon. box
Sturgis Twp. Cor. = North 41.17' (GLO = 40.92')

22" Hick. = S45°W 52.96'
28" Hick. = S21°W 74.40'
30" Oak = S27°E 69.73'
P. Pole = N73°30'W 32.0'

26" Hick. = S21°E 69.73'
18" Hick. = S45°W 52.96'
P. Pole = N68°W 32.07'
P. Pole = N15°W 76.07'

Cor. falls in C of Lakeview Road, in proj. of Fawn River Road to the East & 38' South of Fawn River Road to the West

Set 5/8" x 16" iron w/std. cap over stone in Mon. box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-5) NW Cor. Sec. 18 T8S, R9W

5/8" x 16" iron w/std. cap over stone in Mon. box
N & W 1.0' high in N. side of P. Pole = N74°W 32.00'
N & W 1.5' high in W. side of 30" Oak = S27°E 69.73'
N & W 1.0' high in E. side of 28" Hick. = S21°W 74.40'
N & W 1.0' high in E. side of 22" Hick. = S45°W 52.96'

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON May 10, 1999
Wau CO. REPRESENTATIVE



Signed by J. O. W. Mostrom David W. Mostrom
Surveyor's Michigan License No. 32339

Date 5/20/99

LIBER 5 PAGE 168

REMONUMENTATION