

**SURVEY & REMONUMENTATION**

**FEB 08 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in FAWN RIVER TOWNSHIP  
ST. JOSEPH CO.

**LIBER 5 PAGE 169**

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

7 JUN 1999 10:44:13 AM

CYNTHIA L. JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Located In:	Corner Code #
1. Public Land Survey	T ___ R ___
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S 18 T 8 S R 9 W A-6
	S ___ T ___ R ___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID W. MOSTROM, in a field survey on MAY 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(A-6) WEST 1/4 COR. SEC. 18 T 8 S, R 9 W  
 \*NO GLO CORNER SET \*1960'S ROAD COMMISSION  
 \*1877 SURVEY IN BOOK A, P-262 1/2" PIPE OVER + 'D STONE  
 STONE SET AT PROPORTIONAL IN MON. BOX  
 DISTANCE BETWEEN TOWN STURGIS TWP. COR=NORTH 40.8"  
 CORNER & STATE LINE TRIPLE CHERRY = EAST 73.1'  
 ANCHOR POST = NW 42.7'

\*1976 LCRC IN BOOK 2, P-82  
 FOUND + 'D STONE  
 FENCE LINE = WEST 33.8  
 POLE = NW 73.05'  
 FENCE = WEST 26.0'  
 14" HEDGE = NE 32.35'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND + 'D STONE IN MON. BOX  
 STURGIS TWP. COR. = N06°E 40.9'  
 CORNER FALLS IN PROJ. OF TREELINE TO THE EAST  
 CENTERLINE LAKEVIEW ROAD = EAST 4.5'  
 SET 5/8" X 7" IRON BAR WITH STD. CAP IN CONC. OVER STONE IN MON.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-6) WEST 1/4 COR. SEC. 18, T 8 S, R 9 W  
 5/8" X 7" IRON BAR WITH STD. CAP IN CONC. OVER STONE IN MON. BOX  
 N & W 2.0' HIGH ON E. SIDE OF P. POLE = N15°W 71.15'  
 N & W 2.0' HIGH ON S. SIDE OF 18" MULBERRY = N53°E 56.34'  
 NW COR. GARAGE = S62°E 88.62'  
 N & W 2.0' HIGH ON E. SIDE OF MAILBOX POST = S23°W 52.02'

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 346  
 ON MAY 10, 1999  
 Warr. CO. REPRESENTATIVE

LIBER 5 PAGE 169

Signed by J.W.M. DAVID W. MOSTROM Date MAY 20, 1999  
 Surveyor's Michigan License No. 32339

**REMONUMENTATION**