

SURVEY & REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

For corners in St. Joseph (County) APR 10 1995 Located In: Corner Code ≠#

20 DEC 94 12:39 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

1. Public Land Survey T 8S R 9W B-3
 T R
 T R
 T R
2. Property Controlling In Section S T R
 S T R
3. Miscellaneous Property in Sec. S T R
 S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3	7		8		9		10		11		12		
4	18		17		16		15		14		13		
5	19		20		21		22		23		24		
6	30		29		28		27		26		25		
7													
8	31		32		33		34		35		36		
9													
10													
11													
12													
13													

I, Donald C. Andrews, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Post
1877 NS Andrews Stake no wit. showed distance to west 2787.68'R(2785.68'M) and distance to east 2647.59'R(2653.72'M)
Sayers survey 1972 distance east 2651.35'
Mostrom 1990 reset 1/2" iron(no cap)
LCRC 2, P 212 1/2" rion per L. 360, P.970

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found 1/2" iron. One wit. left in pole south 24.5'R (24.48'M)

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON SEPT. 12, 1994
WCM CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset 1/2" iron with Remon. capped iron.

- 1) utility pole South 24.48'
- 2) NE corner concrete curb S5°E 46.66'
- 3) NW corner concrete curb S10°W 89.35'
- 4) power pole N85°E 76.19'



Signed by Donald C. Andrews

Date 12-12-94

Surveyor's Michigan License No. 33967

REMONUMENTATION

LIBER 4 PAGE 87