

LAND CORNER RECORDATION CERTIFICATE FORM - PAGE 2 OF 2  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in ST. JOSEPH Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)  
FAWN RIVER TWP.

1. Public Land Survey T 8S R 9W \_\_\_\_\_ C-6  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

18 JUN 96 9:16 A.M.

CYNTHIA JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, WAYNE A. MOSTROM, in a field survey on JUNE 7, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

RECORDS OF SAYERS INDICATE ROAD COMM-1960'S  
 THAT PRESENT CORNER WAS USED PIPE IN MON. BOX  
 BY HIM IN NUMEROUS JOBS LISTED R. RAIL FEN. POST = N26°W 54.1'  
 BELOW IN NOTHING BUT A SYMBOL NOTES: 18" OAK STUMP = S69°W 25.75'  
 1962-JOB #4718 TWIN CEDAR = S24°E 70.6'  
 1963-JOB #4920  
 1965-JOB #6017  
 1966-JOB #7214  
 1967-JOB #7333  
 1970-JOB #7969

MOSTROM 1976 & 1992 SURVEY  
LCRC IN 2/82  
IRON IN MON. BOX  
IRON BAR = N31°04'W 63.94'  
IRON BAR = S14°26'W 132.41'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FD. 3/4" PIPE IN MON. BOX OVER NOTCHED STONE  
 RR RAIL POST = N26°W 54.1'  
 TWIN CEDAR = S24°E 70.6'  
 IRON BAR = N31°04'W 63.94'  
 CORNER IS 0.5'W. & 2' N. OF CL - CL INTER OF RDWY'S

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON June 10, 1996  
Was. CO. REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET 5/8"X12" IRON BAR W/STD. CAP IN CONC. IN MON. BOX OVER STONE  
 N & W IN W. SIDE P.P. = S28°E 52.65'  
 NE CORNER HOUSE (FTON.) = S78°W 95.08'  
 N & W IN NE SIDE P.P. = N47°W 39.08'  
 IRON BAR = N31°W 63.94'  
 SE COR RR RAIL POST = N21°W 54.93'  
 N & W IN SE SIDE P.P. = N41°E 48.89'

SURVEY &  
 RE-MONUMENTATION

OCT 03 1996

COMMISSION



LIBER 4 PAGE 231

Signed by Wayne A. Mostrom  
 Surveyor's Michigan License No. 14100

Date JUNE 13, 1996

231