

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1971**

For Corners in

<u>St. Joseph</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>9W</u>	<u>E-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

**LIBER 5 PAGE 229**  
 STATE OF MICHIGAN  
 ST. JOSEPH COUNTY  
 FILED

22 DEC 1999 11:00:09 AM

CYNTHIA L. JARRATT  
 REGISTER OF DEEDS

Register of Deeds Stamp & Filing Number

I, Donald C. Andrews, in a field survey on November, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corners mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monument, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.**

A. Description of original monument and accessories and/or Subsequent restoration:

LCRC 4, PAGE 285

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Remon Capped Iron in Mon Box

The St. Joseph County Land Corners being located were done within specifications for Order "C 2-II". The closest the National Geodetic Reference System monument having a position order of "B" incorporated in the traverse network was the monument having the PID of "AA8117" with Station Name of "IRS-F". The maximum positional error of each Land Corner monument being located would be less than 0.08 feet relative to the connecting HARN control monuments of the National Geodetic Reference System based on a 95% confidence level.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Found Remon Capped Iron in Mon Box

It's coordinates in international feet are: Northing 109533.3529, Easting 12849854.5884

Witness: 10" Maple South 49.75', UP N20°W 113.07', NW Cor. House 87.27', SW Cor. Building N82°E 54.54'

RATIFIED BY PEER GROUP  
 IN ACCORDANCE WITH P.A. 345  
 ON AUG. 12, 1996  
Wren CO. REPRESENTATIVE  
 12/21/99 Wren

Signed by Donald C. Andrews Date 12-20-99

Surveyors Michigan License No. 33967



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983  
 REVISED OCT., 1995

**REMONUMENTATION**