

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
St. Joseph

(County)
Fawn River Twp.
1. Public Land Survey

Located In:	T8S R9W	Corner Code #	K-2
	T R		
	T R		
	T R		
S	T R		
S	T R		
S	T R		
S	T R		

LIBER 5 PAGE 156

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

27 APR 1999 1:21:04 PM

CYNTHIA L. JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Wayne A. Mostrom, in a field survey on March 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1872 Survey in A/188

4" Yellow Oak = N4 1/2°W 36lks (23.76')

4" Yellow Oak = S40°E 38lks (25.08')

Set corner midway between NW & SW Corners of Section 1

Road Commission - 1959

Iron rod in place of Brick found
Anchor Post = North 28.35'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Solid Iron bar 18" long, 12" below surface in pieces of old brick
Anchor Post = North 28.35'

Centerline dirt road = South 2.5'

Corner is in remains of old fence to the North

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON April 19, 1999
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X 24" bar w/std cap in mon. box

N & W In SE Side 10" A.P. = North 28.35'

N & W In E Side RR Tie Post = S10°W 13.35'

N & W In N Side PP = N82°E 108.56'

N & W In W Side PP = N04°E 174.04'

N & W In S Side PP = N84°W 186.64'



LIBER 5 PAGE 156

Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date April 29, 1999

REMONUMENTATION